

Bid Notice Abstract

Request for Quotation (RFQ)

Reference Number	12488963
Procuring Entity	VALENZUELA MEDICAL CENTER
Title	SUPPLY, DELIVERY, TESTING AND COMMISSIONING OF 5HP DUPLEX CONTROLLER, REHABILITATION OF DISCHARGE LINE OF 2PCS GOULDS PUMP (PPR), REPLACEMENT OF FLOAT SWITCH OF OVERHEADTANK
Area of Delivery	Metro Manila

Solicitation Number:	VMC-2025-249	Status	Active
Trade Agreement:	Implementing Rules and Regulations		
Procurement Mode:	Negotiated Procurement - Small Value Procurement (Sec. 53.9)	Associated Components	1
Classification:	Goods	Bid Supplements	0
Category:	General Repair and Maintenance Services		
Approved Budget for the Contract:	PHP 200,000.00	Document Request List	0
Delivery Period:	30 Day/s		
Client Agency:		Date Published	15/10/2025
Contact Person:	Christallyne S. Castro BAC Secretariat Padrigal St., Karuhatan, Valenzuela City Metro Manila Philippines 63-2-2920604 vmc_bac@yahoo.com	Last Updated / Time	15/10/2025 00:00 AM
		Closing Date / Time	20/10/2025 10:00 AM

Description
ITEM NO. UNIT ITEM DESCRIPTION QTY. UNIT COST TOTAL COST
1 lot Supply, Delivery, Testing and Commissioning of 5HP Duplex Controller, Rehabilitation of Discharge Line of 2pcs Goulds Pump (PPR), Replacement of Float Switch of Overheadtank 1 200,000.00 200,000.00
pc Duplex Controller for 5HP Transfer Pump (Components) 1
Specifications:
"NEMA 3R"Enclosure (24"x16"x8")
Mini Breaker 3pole 6amp
Mini Breaker 2pole 6amp
MCCB ABN-53c 30amp 3pole
Contactor MC-18b 220vac coil
OLR MT-32/3H (9-13A)
Selector Switch 3 Position Lays-BD33
Lays-BE102 INC. Contact Switch
Start-Push Button Lays-BA31 Green
Stop-Push Button Lays-BA42 Red
Pilot Light AD16-22DS Green
Pilot Light AD16-22DS Red
Pilot Light AD16-22DS Yellow
Legend Holder H=10 HOA
Legend Holder H-10 Start
Legend Holder H-10 Stop
Legend Holder H-10 Run
Legend Holder H-10 Power On
Legend Holder H-10 Trip
Digital U/O Voltage Relay with Socket AERV-NH 277-519V 3Phase
Liquid Level Relay with Socket AEVR-NH 277 519V, 3Phase
Liquid Level Relay with Socket AFR-1 220Vac Electrodes
pc Float Switch 1
Alternator 220VAC CA2SK20M7
505-4PL 220VAC Control Relay 4NO,4NC, Socket KMY4
On-delay Timer with Socket AH3-N2 220vac
Scope of Works:
1. Mobilization of Manpower, Tools and Equipment

2. Installation of New Duplex Controller & Float Switch at Overheadtank
3. Testing and Commissioning
4. Turnover to the authorized personnel
5. Final Acceptance: Submission of Completion Report and Warranty Certificate
Delivery Period:30 Calendar Days upon receive of PO and payment
Warranty: six (6) months from the date of delivery
GRAND TOTAL 200,000.00
Other Information
A copy of your legal requirements (SEC/DTI, Business/Mayor’s Permit with Official Receipt, Platinum PhilGEPS Certificate, Tax Clearance, BIR Certificate of Registration (COR), Brochure (if applicable) and Original Omnibus Sworn Sta8tement) is also required to be submitted along with your quotation/proposal.
Quotations may be submitted manually at the office of the BAC Secretariat, BAC Office, Valenzuela Medical Center, Padrigal St., Karuhatan, Valenzuela City or send through email at vmc.bac2025@gmail.com.

Created by	Christallyne S. Castro
Date Created	14/10/2025

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.