



GEP

Philippine Government Electronic Procurement System

Central Portal for
Philippine Government
Procurement Opportunities

Help

Bid Notice Abstract

Request for Quotation (RFQ)

Reference Number 11746069
Procuring Entity VALENZUELA MEDICAL CENTER
Title 1 LOT COMPLETE SUPPLY OF LABOR, TOOLS, AND EQUIPMENT FOR THE REWINDING OF FIRE PUMP OF VMC, MOTORPOOL BUILDING
Area of Delivery Metro Manila

Solicitation Number:	VMC-2025-070	Status	Active
Trade Agreement:	Implementing Rules and Regulations		
Procurement Mode:	Negotiated Procurement - Small Value Procurement (Sec. 53.9)	Associated Components	1
Classification:	Goods	Bid Supplements	0
Category:	Fire Fighting & Rescue and Safety Equipment		
Approved Budget for the Contract:	PHP 157,383.33	Document Request List	3
Delivery Period:	30 Day/s		
Client Agency:		Date Published	11/02/2025
Contact Person:	LESTER JOHN JAKE R DIVINO BAC SECRETARIAT Padrigal St., Karuhatan, Valenzuela City Metro Manila Philippines 63-2-2920604 vmc_bac@yahoo.com	Last Updated / Time	11/02/2025 00:00 AM
		Closing Date / Time	14/02/2025 10:00 AM

Description	
STOCK/ PROPERTY NO. UNIT ITEM DESCRIPTION QTY. UNIT COST TOTAL COST	
Complete Supply of Labor, Tools and Equipment for the Rewinding of Fire Pump of Valenzuela Medical Center - MOTORPOOL BUILDING	
lot REWINDING OF FIRE PUMP MOTOR 1 157,383.33 157,383.33	
Specifications: Pump Model: XA65/16-S30 Capacity: 30HP, 500GPM, 60psi Voltage: 380/220V Current: 34.7/59.9Ampere Frequency: 60Hz, 3Phase Weight: 135Kg Speed: 3500RPM	
Scope of Works: 1. Coordination with end-user prior to pull out the motor. 2. Dismantling of the unit. 3. Conduct Initial Static Instrumentation Test: - Insulation Resistance Test - Winding Resistance Test 4. Removal of burnt-out windings and note original winding data and size of wires. 5. Evaluate and note the cause of burnt-out winding. 6. Evaluate mechanical problem arise during the course of implementation. 7. Cleaning of slots.	

- | | |
|--|--|
| <div data-bbox="178 181 990 695" data-label="List-Group"><ol style="list-style-type: none">8. Check and conduct hot core test to check the hot spots.9. Apply Red varnish to the stator core.10. Insertion of new winding according to its original winding data.11. Oven bake to cure moisture and monitor insulation before varnishing.12. Oven bake to cure varnished.13. Clean and scrape out exist varnished.14. Replacement of bearing.15. Assemble the unit.16. Conduct final static Instrumentation Test:<ul style="list-style-type: none">- Insulation Resistance Test- Winding Resistance Test17. Clean and prepare for painting and packaging.18. Prepare reports prior to delivery.19. Coordination with the end-user for the delivery schedule.20. Deliver the unit.21. Installation of the Existing Fire Pump22. Conduct Testing and Commissioning23. Turnover to the authorized personnel24. Final Acceptance: Submission of completion report<div data-bbox="178 710 735 819" data-label="Text"><p>Delivery: 30 working days upon receive of JO
Warranty: Three (3) months on supplies and labor
Duration of Work: One (1) week
***** nothing follows *****</p></div><div data-bbox="178 839 316 872" data-label="Text"><p>157,383.33</p></div><div data-bbox="178 892 1445 986" data-label="Text"><p>A copy of your UPDATED legal requirements (Certificate of Registration from BIR, SEC/DTI, Business/Mayor's Permit with Official Receipt, PhilGEPS Certificate, Tax Clearance, Audited FS with 2023 ITR, and Omnibus Sworn Statement) is also required to be submitted along with your quotation/proposal.</p></div><div data-bbox="178 971 410 1001" data-label="Section-Header"><p>Other Information</p></div><div data-bbox="178 999 1433 1096" data-label="Text"><p>Quotations may be submitted manually at the office of the BAC Secretariat, BAC Office, Valenzuela Medical Center, Padrigal St., Karuhatan, Valenzuela City., through email to vmc_bac@yahoo.com. For any clarification, you may call Lester John Jake R. Divino at telephone no. 294-46-25 or via email at vmc_bac@yahoo.com.</p></div><div data-bbox="178 1101 308 1133" data-label="Text"><p>Thank you.</p></div></div> | |
|--|--|

<div data-bbox="178 1181 763 1216" data-label="Text"><p>Created by LESTER JOHN JAKE R DIVINO</p></div>	
---	--

<div data-bbox="178 1223 573 1258" data-label="Text"><p>Date Created 10/02/2025</p></div>	
--	--

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.